



Stormcloud Brewing

Frankfort, MI | Industrial

THE CHALLENGE

Stormcloud was growing. They added a new Production Brewery and Tasting room that opened on May 25th of 2018. The production facility was constructed using 10" insulated composite wall panels.

THE SOLUTION

The project consisted of about 11,800 sf of wall panel. The precast panels were installed in three days. Kerkstra also supplied hollowcore plank for this project. The plank was used to provide a mezzanine above the office, lab and tasting room. 10" hollowcore plank was used due to its load capacity for storing brewing supplies.

THE RESULT

This new facility has the capacity to brew 4500 barrels of beer per year. Designed by Byce & Associates, Inc. of Kalamazoo, the production brewery houses brewing, fermentation, packaging, cold storage, and all shipping and receiving processes.

“

The owners of Stormcloud Brewing wanted a cost effective, low maintenance product for the walls within their new brewery facility. We turned to Kerkstra for the solution. Having worked with Kerkstra on several projects, we knew their precast wall panels would be the right choice, especially for the winter construction time frame we were facing. As expected Kerkstra delivered.

Jody Bergman
Comstock Construction



Total Product Square Footage: 14,068